







CONFIGURATION LIST





| NO. | Parts | SPECIFICATION | Size | | Photo for sample | Remark |
|--------------------------------------|--|---|---------------------------------|---|---|--|
| 1. Main structure | | | | | | |
| 1 | Main structure | Steel column | □120*120*2.0mm | √ | | Weathering resistance steel 50 years |
| 2 | | Steel beam | □120*120*2.0mm | √ | | |
| 3 | | Floor steel beam | C120*48.5*1.5mm,C117*48*8*1.5mm | √ | | |
| 4 | | Roof frame | C100*38.5*1.5mm,C97*40*1.5mm | √ | | |
| 5 | | Ceiling keel | C80*40*0.8mm | √ | | |
| 2. Steel structure antiseptis | | | | | | |
| 1 | Anti-corrosion treatment of the exterior surface | Surface zinc plating, thickness: 0.12mm | | √ | | Antiseptis: 50 years |
| 3. Floor structure | | | | | | |
| 1 | Base material/Insulation | PU foam board | Thickness : 70mm | √ |  | |
| 2 | Floor surface | 5mm PVC Flooring | | √ |  | Living zone |



| 4. Wall structure | | | | | | | |
|---------------------------|--|-------------------|--|-----------|---|---|--|
| 1 | Wall panel | Interior | Wooden Aluminum alloy coating | 0.5mm | √ |  | |
| | | Exterior | Wooden Aluminum alloy fluorocarbon coating | 0.8mm | √ | | |
| | | Inside | PU foam board | 100mm | √ | | |
| 5. Roof ceiling structure | | | | | | | |
| 1 | Roof | Heat preservation | PU foam board | 100mm | |  | |
| 2 | | Waterproof | waterproof roll | | |  | |
| 3 | | Roof surface | Asphalt shingle roof | | |  | |
| 4 | Ceiling | Interior ceiling | WPC ceiling | 120*100mm | |  | |
| 6. Electric System | | | | | | | |
| 1 | LED Lighting (Main lamp and lighting lamp) | | | | √ | | |
| 2 | Switch, socket concealed installation into wall body | | | | √ | | |

| | | | | | | |
|-----------------------------|--------------------|---------|---|-------------------------|----|---|
| 13 | | | Door trim concealed installation into wall body | -1 | | |
| 14 | | | Decorative door and window lockage switch | -1 | | |
| 4.2 Internal Windows | | | | | | |
| 15 | Wood | Windows | Aluminium alloy door | W100-1000mm | -1 |  |
| | | Windows | Aluminium alloy door | W100-1000mm | -1 | |
| 16 | Steel Aluminium | | Enter door lock | requisite used for fire | -1 |  |
| 17 | | | Door stop/rod | | -1 |  |
| 18 | | | Door stopper | | -1 |  |
| 19 | | | Stop | | -1 |  |
| 20 | | | | | -1 |  |

| | | | | | | |
|---|--------|--|-------------|---|--|--|
| 7 | Window | 1.5mm Aluminum wooden windows, double tempered glass | 1200*1800mm | √ |  | |
|---|--------|--|-------------|---|--|--|

8. Accessories

| | | | | | | |
|--|----------------|--|---------------------------------|---|---|--|
| | Basin | | / | √ |  | |
| | | | | √ |  | |
| | Toilet bowl | | / | √ |  | |
| | Bathroom glass | | Aluminum frame, 8mm Scrub glass | √ |  | |

| | | | | | | | |
|---|-----------------------------|------------------------------|-------------|----------|---|---|--|
| 3 | Outdoor balcony accessories | Decking | WPC decking | 147*23MM | √ |  | |
| | | Light steel keel for decking | | | √ |  | |

Prefab house quotation

| No. | Modle Code | Covered area with balcony | With furniture | Aluminum alloy wall Price EXW (unit) | Functional layout |
|-----|------------|---------------------------|----------------|--------------------------------------|---|
| 1 | MB-J | 35 sqm | No | USD 32400 | 1 bedroom+1 bathroom+1 kitchen(with cabinet)+1 balcony |

| | |
|--------------|--|
| Note: | <p>1. Quotation includes bathroom hardware sanitary ware, glass shower room, hand washing cabinet toilet accessories and PVC flooring, aluminum alloy door and window etc, droplight and LED light for all house.</p> <p>2. consider the different country have different local standards about electricity and water, quotation don't include electricity wire and water pipe, you arrange workers responsible for water and electricity connect by your side, and buy wire and pipes by yourself, we will provide other material material of the house inculding socket and make the hole of the wall.</p> |
|--------------|--|

| | |
|--|---|
| | <p>1. This quotation is for EX Works, and valid for 60 days</p> <p>2.This quotation don't include fumiture, installation, electrical and foundation</p> <p>3. If you need to do the FOB and CNF, increase the costs alone.</p> <p>4.This offer does not contain installation, can provide installation guide figure, if you need my company send installation instructor, need to increase the cost</p> <p>5. Lead time: 45days -50 days</p> <p>6. PAYMENT: 50% T/T in advance, shipments before 50% balance complete</p> |
|--|---|



