ITEM	DESCRIPTION		Picture	QTY	UNIT		
I	Journey Living House 6000*9000+6000*3000mm	light steel with steel column		1	set	$29,980.00	
1.Frame							
1.1	Light steel structure frame	275g/m2 Galvanized and Aluminized LGC Framing Metalcon C 903812,1.0mm		2.99	ton		
1.2	Steel column and connection	100*100*3mm		0.8	ton		
1.3	Screws			1	pack		
1.4	connection parts			1	pack		
1.5	anchor adjusting bolt	not needed if the ground is horizontal by cement		40	pack		
1.6	Steel Column and connection 100*100*3mm			1.5	ton		

2.Wall and decoration							
2.1	OSB board	1200*2440*9mm		406	M2		
2.2	Rock wool	40g/cm3 100mm		132	M2		
2.3	Decoration mat			20	M2		
2.4	ALU broken bridge windows with 2 layers tempered glass			20	M2		
2.5	PU decoration panel			236	M2		
2.6	PU decoration panel			236	M2		
2.7	ALU edgefold			1	set		
2.8	indoor wood floor			71	M2		
2.9	outdoor balcony	Sauna board		19.6	M2		
2.1	outdoor balcony	plastic wood board		6	M2		
2.11	integrated toliet			1	set		
2.12	Pipe type handrail			10	set		
2.13	Spiral staircase/glass staircase			1	set		
2.14	Ceiling（livingroom & toleit			21	M2		
3.Water and electricity							

3.1	Light			1	set		
3.2	Light line			1	set		
3.3	Distribution box of 10 circuit	ABB		1	set		
3.4	electric cable and pipes			1	set		
3.5	spot light and sockets	15 sockets		15	set		
3.6	Switch	86*86mm		5	set		
3.7	spotlight			5	set		
II	Shipping cost		40GP	0	set		
III	Attentions						

III.1 The costs of foundation is not included.150mm concrete foundation is necessary.If the foundation not horizontal,steel fashion steel column platform(item 1.5#,1.6#) is needed then.

III.2 Labor cost(installation) not included yet.

III.3 Costs for fire fighting system, security system are not included.

III.4 The framework for professional design of light steel structure, after many authentication, windproof seismic termite resistance, the main structure service life can reach at least 70 years

III.5 Loading:1x40GP can load 1 set of aboved materials

III.6 Ware note:if customer have add new requirements,drawing and prices should be negotiated.