

List of Component

	<b>Title of Unit</b>	<b>Supplier</b>	<b>Note</b>	
	Transfomer UMD	Kraftelektronik		
	UMD и UPS	Kraftelektronik		
	Frecuency Converter	Siemens Drive Technologies AB	SINAMICS G150	
	Battery	KraftPowercon AB		
	Relay Protection	Siemens AB	SIPROTEC Multifunctional Machine Protection 7UM62 V4.6	
	Flame Monitoring	BFI Automation		
	Speed and Overspeed Monitoring System	Jaquet AG		
	Servo controller MSD3200	Moog		
	Turbine speed & Vibration Monitoring System	Bently Nevada		
	Control System	Siemens		
	Seal Air Cooler	AEL Apparatebau GmbH Leisnig		
	Purge Air Cooler	AEL Apparatebau GmbH Leisnig		
	Clutch	SSS Gears LTD		
	Coupling	Euroflex Transmissions (India)		
	Start Motor	Siemens		
	Gear	Voith Turbo BHS Getriebe GmbH		
	Coupling	Euroflex Transmissions (India)		
	Air Intake System	Camfil Farr Pow. Syst.		
	Plenum	HIAK		
	Bleed Valve	Gustaf Fagerberg AB		
	Governing Valve	Coor Service Management		
	Shut Off Damper	Camfil Farr Pow. Syst.	Air Intake System	
	Actuator	SKF Multitec		

#### 4.6.4 Inspection and Test Plans

The Contractor shall supply proposed Inspection & Test Plans (ITPs) for approval in accordance (as far as reasonably practicable) with AS/NZS 9001 (2016). ITPs shall nominate the inspection, hold and release points proposed by the Contractor or its subcontractors. Such plan(s) shall identify the records to be maintained under the Contract and also indicate the manner of formal acceptance and release. Subcontractor ITPs shall be referenced on the Contractor's Master Controlling ITP and shall be checked and endorsed by the Owner prior to implementation by the Contractor.

Proposed ITPs shall be submitted to the Owner in sufficient time to allow the Owner to assess their suitability for use in relation to the Contract and to review the inspection, hold and release points required by the Owner.

The Contractor shall ensure that all prior inspections and tests have been carried out in accordance with the approved ITPs and the necessary records are available before requesting attendance by the Owner at an inspection or hold point for ITP sign off.

#### 4.7 Certificate of Completion

A certificate of completion will be provided when the Contractor fulfils the following:

- a) Turbine works have been completed and all Owner permits returned to the Owner
- b) Turbine is performing as specified
- c) All defects have been rectified
- d) All surplus parts and those removed from the turbine have been returned to the Owner
- e) Turbine completes a 24hour operational run which satisfies the warranted performance criteria
- f) All QA documentation and ITPs completed and copy provided to the Owner
- g) Preliminary outage report submitted to the Owner.

A final outage report is to be provided by the Contractor within 4 weeks after comments on the preliminary report have been received from the Owner.

	Liquid Fuel Unit	JohSjö System AB		
	Three Way Valve	Axel Larsson		
	Flow Meter	Endress & Hauser AB		
	Gas Fuel Unit #1 & #2	Eltacon Engineering		
	Actuator IGV	SKF Multitec AB		
	Dosage Unit	Joh Sjö Industri AB		
	Water Injection System	JohSjö System AB		
	Lube Oil Unit	AEL Apparatebau GmbH Leisnig		
	Lube Oil Cooler	Tranter		
	Generator	ABB Automation		
	Automatic Voltage Regulator	ABB Automation		